

# Validation Test Report

# 250 AMPIP POD

June 30, 2016.



Tested &	Reviewed	Approved	Test Date	From June 28, 2016
Reported By	By	By		To June 30, 2016
3	(i)	after a	Classification	Unrestricted

## • TE CONNECTIVITY RELIABILITY TEST REPORT

Test Name: Validation for 250 AMPIP POD.

#### 1. Introduction

#### 1-1 Purpose

Testing was performed on the 250 AMPIP POD to determine

if it conformance to the requirements of Product Specification 108-5100, Rev.B1

This experiment is intended to verify the reliability of the new HSG material.

(Applied resin: PA66, PN: 2136403-1)

#### 1-2 Scope

This report covers the electrical, mechanical, environmental performance requirements of the 250 AMPIP POD.

The testing was performed between June 28, 2016 and June 30, 2016.

#### 1-3 Test Samples

The test samples were randomly selected from normal current production lots.

P/N	Description						
7-171706-1	250 AMPIP POD						
2232112-1	250 SERIES FASTON RECEPTACLE						

#### 1-4 Conclusion

The 250 AMPIP POD meets the electrical, mechanical performance requirements of Product Specification 108-5100, Rev.B1

#### 1-5 Attachment

1) Test Result

# 1) Test Result

## - Test Group 1

NO.	Test Items	Test Condition	Acceptance criteria	Unit		Test Result								
					Wire (AWG)	S1	S2	S3	S4	<b>S</b> 5	Min.	Max.	Avg.	Judgment
1	Contact Retention Force	Initial	8 kgf Min.	kgf	-	22.17	23.18	21.97	22.09	22.35	21.97	23.18	22.35	ОК

# - Test Group 2

NO.	Test Items	Test Condition	Acceptance criteria	Unit	Test Result									
					Wire (AWG)	S1	S2	S3	S4	S5	Min.	Max.	Avg.	Judgment
1	Insulation Resistance	Initial	500 MΩ Min.	GΩ	ı	9.11	9.46	8.79	9.09	8.96	8.79	9.46	9.08	ОК
2	Dielectric Strength	Initial	No abnormalities shall be evident.	-	,	ОК	ОК	ОК	ОК	OK	1	1	-	OK